

BAY ARÉA RAPID TRANSIT DISTRICT 800 Madison Street Oakland, California 94807 Telephone 465-4100

BACKGROUND INFORMATION

BART SYSTEM FACT SHEET

BOARD OF DIRECTORS

9 members representing 9 election districts in the three counties BART serves-3 from San Francisco, 4 from Alameda County, and 2 from Contra Costa County.

MILEAGE

71 total - (approximately 19 subway and tunnel; 23 aerial; 25 surface; 4 of Trans-Bay Tube.) Also, 4 additional miles of S. F. Municipal Railway track.

STATIONS

34 BART stations - 14 subway, 13 aerial, 7 surface. 4 S. F. Muni stations - 3 subway, 1 surface.

STATION FEATURES

Custom designed by 16 architectural and 8 landscaping firms. Parking at 22 stations; capacity ranges from 240 to 1400 spaces; totaling 17,692 spaces.

Bicycle parking at all suburban stations. Large, full-color maps in each station.

Computerized train destination signs on platforms alert passengers to train arrivals; also carry news, advertising and public information messages between train arrivals

Special elevators and ramps for handicapped. Mosaics, sculpture, fountains, landscaping.

TRANS-BAY TUBE

3.6 miles, twin-section, concrete and steel. 24' H \times 48' W, buried in trench 75'-135' underwater. High earthquake tolerance.

TRAINS

Third rail propulsion power is 1000-volt DC electricity.

Propulsion - one 150-HP motor per axle, four motors per car.

Features - aluminum body, 72 seats, carpeted, air-conditioned, tinted windows.

Car - 70' long, 10'6" high, 10'6" wide, headroom 6'9".

Track gauge - 5'6" wide for stability. (standard: 4'8½")

Number of cars - 450 vehicles for initial full operation; built by Rohr Industries.

Speed - 80 MPH maximum, 39 MPH average, including 20-second station stops.

Acceleration and deceleration - 3 MPH per second maximum.

76 01477

INSTITUTE OF GOVERNMENTAL STUDIES LIBRARY

MAR - 7 2020

UNIVERSITY OF CALIFORNIA

AUTOMATIC TRAIN CONTROL

Twin train control computers (one for back-up) - at Lake Merritt Station, Oakland; built by Westinghouse.

Car-borne equipment - console monitored by attendant who can override automatic control in emergencies to stop train, or run at 25 MPH in manual mode.

Stations and wayside - network of control devices and track circuits controlling train speeds, stops, and safe spacing.

AUTOMATIC FARE COLLECTION

Station equipment - IBM change and ticket vending machines and gates. Entry gate - records time, date, station; returns ticket.

Exit gate - computes required fare, takes exact-fare ticket, instructs if additional payment needed, or deducts proper amount from multiride ticket.

Ticket - credit-card size, magnetically encoded or "stored" with up to \$20 of fares. Machines automatically deduct trip fares from stored fare value on ticket.

BASIC FARE

Minimum 25¢ to maximum \$1.45 one-way, based on trip miles.

SPECIAL FARES

All discounted tickets must be purchased at local banks only, not at BART stations.

Children under 5 ride free.

Children 5 through 12 can purchase a ticket worth \$6.00 for \$1.50. Field Trips. Students (under 18) on an organized field trip receive a 75% discount.

Senior Citizens 65 and over can purchase a ticket worth \$6.00 for just 60¢.

Disabled persons can purchase a \$6.00 ticket for \$1.50.

WEEKDAY TRAIN SCHEDULES 6 a.m. - 8 p.m.

Trains are dispatched between Richmond and Fremont every 12 minutes; Between Fremont and Daly City every 12 minutes; and between Daly City and Concord every 12 minutes.

West Bay Line (between Daly City, San Francisco, West Oakland) - 2 minutes peak hours; 4 minutes off-peak hours; 20 minutes late night.

MAXIMUM MOVING CAPACITY

21,600 seated people, per hour, one way, at 2-minute headways (equal to maximum people 10 lanes of freeway traffic can move in peak hours).

Digitized by the Internet Archive in 2024 with funding from State of California and California State Library

ROUTES AND TRAVEL TIMES

Radiating in rough "X" shape from Oakland City Center-12th Street Station:

South to Fremont - 24 miles - 30 minutes.

North to Richmond - 11 miles - 19 minutes.

East to Concord - 21 miles - 27 minutes. West to Daly City - 15 miles - 23 minutes.

(4 miles of streetcar line in San Francisco complete 75 miles in BART project.)

ESTIMATED COST TO COMPLETE SYSTEM: \$1.6 billion.

Sources of funding:

1962 bond election	\$792	million
interest earnings, other local sources	186	million
one-half percent sales tax	150	million
bridge tolls (construction of Trans-Bay Tube)	176	million
federal grants	315	million

MAJOR EQUIPMENT CONTRACTS

Rolling Stock - Rohr Industries. 450 cars at a cost of \$162 million. Let July 1969.

ATO System - Westinghouse Corporation. Initial contract was for \$26,199,959.

Let March 1967. Change orders amounting to \$5,831,273 brings total to \$32,751,604.24.

AFC (FARE COLLECTION) - IBM. Initial contract was for \$4,955,000. Let June 1968. Change orders to date bring contract total to \$6,253,332.72.

AFC (ADDITIONAL) - Western Data Products Inc. \$5,058,860. Let March 1974.

#



INSTITUTE OF GOVERNMENTAL STUDIES LIBRARY

MAR - 7 2020

UNIVERSITY OF CALIFORNIA